

All Terrain LANDSCAPING

Bid ID #: 1374

Helping you &
your landscaping *Shine*

Prepared for:

Rob RETONDO

5312 W 9TH ST DR STE 120

GREELEY, CO 80634

Created by:

Bid Awarded To Not Set :)

robretondo@atpslandscaping.com



All Terrain
LANDSCAPING

970-304-1183 atpslandscaping.com
5312 W. 9th St. Dr., Suite 120, Greeley, CO. 80634

About All Terrain Landscaping

Our mission is to help you look great.

All Terrain Landscaping began with a simple sprinkler job for a family friend. After earning multiple degrees, we launched the company, focusing on hand-dug ponds and sprinklers. Our first company vehicle was an '84 Mustang. The business grew quickly, and soon we were full-time landscapers. With a strong work ethic and a dedicated team, we became the largest lawn service and snow removal company in Greeley, eventually expanding into Fort Collins, Boulder, and beyond.

View Our Work



Project Details

-Installation of the planting beds to include:

- Demo, haul off, and disposal of 0 SF of existing landscape for a 0 LF by 0 tall retaining wall

-Installation of a core drilled boulder water feature to include:

- Excavation of a 5' by 5' by 2' deep area
- Installation of 169 SF of 40 MIL EPDM pond liner
- Installation of pump and vault
- Installation of _____ tons of 1 ½" local river rock
- Installation of _____ tons of 2"-4" cobble
- Installation of _____ tons of pea gravel
- Installation of _____ tons of boulders
- Installation of an automatic fill valve from the irrigation system

-Installation of pavers to include:

- Installation of _____ tons of road base and _____ tons of sand for base materials
- Installation of Versalok/ Allan block retaining wall blocks/ timbers and _____ block cap for a _____ LF by _____ tall retaining wall
- Installation of _____ square feet of pavers (color TBD)
- Installation of _____ bags of polymeric sand
- Installation of _____ downspout drains
- Installation of a 4' diameter by 2' tall gas/ wood burning fire pit to include:
 - Installation of CMU and veneer
 - Installation of a gas line
 - Installation of a match light burner and glass

- Installation of _____ LF of 18" CMU and veneer seat wall with veneer cap

- Installation of a _____ LF by 3' by 3' tall outdoor kitchen to include:

- Installation of CMU and veneer
- Installation of _____ SF of granite counter (level 1, rounded edges)
- Installation of 36" AOG NBT gas grill
- Installation of single access door
- Installation of double access doors
- Installation of AOG side burner