

All Terrain LANDSCAPING

Bid ID #: 16432

Helping you &
your landscaping *Shine*

Prepared for:

Old Town North The Summit HOA Management Company

749 Jerome Street

Fort Collins, CO 80524

(970)795-2519

marah@thesummitmgt.com

Created by:

Derrick Bleeker

derrickbleeker@atpslandscaping.com



All Terrain
LANDSCAPING

970-304-1183 atpslandscaping.com
5312 W. 9th St. Dr., Suite 120, Greeley, CO. 80634

About All Terrain Landscaping

Our mission is to help you look great.

All Terrain Landscaping began with a simple sprinkler job for a family friend. After earning multiple degrees, we launched the company, focusing on hand-dug ponds and sprinklers. Our first company vehicle was an '84 Mustang. The business grew quickly, and soon we were full-time landscapers. With a strong work ethic and a dedicated team, we became the largest lawn service and snow removal company in Greeley, eventually expanding into Fort Collins, Boulder, and beyond.



View Our Work



Project Details

Demo

- Demo, haul off, and disposal of existing landscape

Sod

- Installation of 2384 square of blue grass sod
- Rototilling
- Installation of final grade
- Installation of 8 yards of compost
- Installation of 126 linear feet of metal roll top edging

Garden Area

- Installation of 25 tons of 3/8" grey granite chip
- Installation of 1577 square feet of landscape fabric
- Installation of 188 linear feet of metal roll top edging
- Installation of 22 yards of planters mix for raised beds
- Installation of 11 6'x3'x2' stock tanks
- Installation of 1 8' diameter stock toank

Rock Bed

- Installation of 36 tons of 1-1/2" local river rock
- Installation of 3,130 square feet of landscape fabric
- Installation of 120 linear feet of metal roll top edging
- Installation of 338 square feet of 4" thick concrete (grey with broom finish)

Plants

Installation of 4 - 2" caliper trees

- Installation of 12 - 5 gallon shrubs
- Installation of 57 - 1 gallon perennials

Irrigation

- PVC mainline -Schedule 80 manifolds- Rotor style irrigation heads with 2 drip zones included

•PVC mainline •Schedule 80 manifolds- Rotor style irrigation heads with 2 drip zones included