

All Terrain LANDSCAPING

Bid ID #: 16511

Helping you &
your landscaping *Shine*

Prepared for:

Jeff Ekstrand

1267 Smoky River Dr

Windsor, CO 80550

(720)626-5116

Jekstrand20@gmail.com

Created by:

Kaylor Werner

kaylorwerner@atpslandscaping.com



All Terrain
LANDSCAPING

970-304-1183 atpslandscaping.com
5312 W. 9th St. Dr., Suite 120, Greeley, CO. 80634

About All Terrain Landscaping

Our mission is to help you look great.

All Terrain Landscaping began with a simple sprinkler job for a family friend. After earning multiple degrees, we launched the company, focusing on hand-dug ponds and sprinklers. Our first company vehicle was an '84 Mustang. The business grew quickly, and soon we were full-time landscapers. With a strong work ethic and a dedicated team, we became the largest lawn service and snow removal company in Greeley, eventually expanding into Fort Collins, Boulder, and beyond.



View Our Work



Project Details

Sport Court Wall

Installation of Retaining Wall to include:

- Installation of 3 ton of road base for base materials
- Installation of 3 ton of sand for base materials
- Installation of 148 retaining wall blocks and 55 block caps for a 55 LF by 2-foot-tall retaining wall

Trampoline Wall

Installation of Retaining Wall to include:

- Installation of 3 tons of road base for base materials
- Installation of 3 tons of sand for base materials
- Installation of 76 retaining wall blocks and 28 block caps for a 28 LF by 2-foot-tall retaining wall

Firepit Wall

Installation of Retaining Wall to include:

- Installation of 3 tons of road base for base materials
- Installation of 3 tons of sand for base materials
- Installation of 144 retaining wall blocks and 53 block caps for a 53 LF by 2-foot-tall retaining wall

Planting Bed

- Installation of 14.5 tons of 1-1/2" mountain granite river rock
- Installation of 3,660 square feet of landscape fabric
- Installation of 11 tons of 2"-4" white cobble
- Installation of 22.5 yards of cascade cedar mulch
- Installation of 5.5 tons of 3/8" grey granite chip
- Installation of 492 linear feet of metal roll top edging

Raised Planters

- Installation of 1 ton of road base for base materials
- Installation of 1 ton of sand for base materials
- Installation of 24 - 6" by 6" by 8' long timbers
- Installation of 3 yards of topsoil for berm