

All Terrain LANDSCAPING

Bid ID #: 17417

Helping you &
your landscaping *Shine*

Prepared for:

Michael Dejong
946 Pine St.
Steamboat Springs, CO 80487
(970)846-3661
michael.dejong@steamboatsir.com

Created by:

Derrick Bleeker
derrickbleeker@atpslandscaping.com



All Terrain
LANDSCAPING

970-304-1183 atpslandscaping.com
5312 W. 9th St. Dr., Suite 120, Greeley, CO. 80634

About All Terrain Landscaping

Our mission is to help you look great.

All Terrain Landscaping began with a simple sprinkler job for a family friend. After earning multiple degrees, we launched the company, focusing on hand-dug ponds and sprinklers. Our first company vehicle was an '84 Mustang. The business grew quickly, and soon we were full-time landscapers. With a strong work ethic and a dedicated team, we became the largest lawn service and snow removal company in Greeley, eventually expanding into Fort Collins, Boulder, and beyond.



View Our Work



Project Details

Sod

- Installation of 6064 SQFT of blue grass sod
- Rototilling
- Installation of final grade
- Installation of 19.00 yards of compost
- Installation of 591 linear feet of metal roll top edging

Pavers

- Demo, haul off, and disposal of 348 square feet of existing patio
- Installation of 348 square feet of pavers (color TBD)
- Installation of 5 bags of polymeric sand
- Installation of 2 tons of sand for base material
- Installation of 14 tons of road base for base material
- For a 26.00 LF by 2.50 tall retaining wall/seat wall
 - Installation of 90.00 retaining wall blocks Keystone Steamboat smooth face
 - Installation of 26.00 block caps Keystone Steamboat smooth face
- Installation of 1.00 tons of road base for base material
- Installation of 4 tons of 1-1/2" local river rock behind wall for drainage
- Installation of 1.00 tons of sand for base material
- Installation of 18 pieces flagstone for steps to shed and lower patio from front

Plants

- Installation of 35 - 5-gallon shrubs
- Installation of 205 - 1-gallon perennials
- Installation of 1 - 2" caliper trees
- Installation of 2 - 15-gallon trees
- Installation of 1 - 8' tree
- Installation of 1 - 6' tree

Planting Bed

- Installation of 36.50 tons of 1-1/2" grey river rock (labor only no material)
- Installation of 5,699 square feet of landscape fabric
- Installation of 116.00 owner provided retaining wall blocks